

BLM-CARLSBAD FIELD OFFICE

Form 3160-3
(August 2007)

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
OMB No. 1004-0137
Expires July 31, 2010

5. Lease Serial No.
SHL:NM NM114347 BHL:NM NM120349

6. If Indian, Allottee or Tribe Name
N/A

7. If Unit or CA Agreement, Name and No.
N/A

8. Lease Name and Well No.
CARBON VALLEY 26 FED COM #1H

9. API Well No.

10. Field and Pool, or Exploratory
DOG CANYON; WOLFCAMP

11. Sec., T. R. M. or Blk. and Survey or Area
SEC. 26, T16S, R27E

12. County or Parish
EDDY

13. State
NM

NO NOS APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: ☒ DRILL ☐ REENTER

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☐ Single Zone ☐ Multiple Zone

2. Name of Operator
MURCHISON OIL & GAS, INC.

3a. Address 1100 MIRA VISTA BLVD.
PLANO, TX. 75093-4698

3b. Phone No. (include area code)
972-931-0700

4. Location of Well (Report location clearly and in accordance with any State requirements.)*
At surface 1980' FSL & 250' FEL, UNIT I
At proposed prod. zone 1980' FSL & 330' FWL, UNIT L

14. Distance in miles and direction from nearest town or post office*
APPROXIMATELY 11 MILES NE OF ARTESIA, NEW MEXICO

15. Distance from proposed* location to nearest property or lease line, ft. 250' AT SURFACE
526' AT TOP WOLFCAMP
(Also to nearest drig. unit line, if any)

16. No. of acres in lease
120

17. Spacing Unit dedicated to this well
160

18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. N/A

19. Proposed Depth
10705' MD 6235' TVD
PILOT 6600' TVD

20. BLM/BIA Bond No. on file
NM2163

21. Elevations (Show whether DF, KDB, RT, GL, etc.)
3491' GL


22. Approximate date work will start*
04/01/2010

23. Estimated duration
30 DAYS

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

| | | |
|---|--|--------------------|
| 25. Signature  | Name (Printed/Typed) A. ARNOLD NALL | Date 01/22/2010 |
|---|--|--------------------|

Title
VP OPERATIONS

| | | |
|-------------------------|----------------------|------|
| Approved by (Signature) | Name (Printed/Typed) | Date |
|-------------------------|----------------------|------|

| | |
|-------|--------|
| Title | Office |
|-------|--------|

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

STATEMENT ACCEPTING RESPONSIBILITY FOR OPERATIONS

Murchison Oil & Gas Inc.
1100 Mira Vista Boulevard
Plano, Texas 75093-4698

The undersigned accepts all applicable terms, conditions, stipulations and restrictions covering operations conducted on the leased land or portion thereof, as described below:

| | |
|-------------------------------|--|
| Lease No: | SHL: LS # NMNM 114347 BHL: LS #NMNM 120349 |
| Well Name: | Carbon Valley 26 Fed Com #1-H |
| Legal Description of Land: | SL: 1980' FSL & 250' FEL, Unit I BHL: 1980' FSL & 330' FWL, Unit L Sec 26, T16S, R27E Eddy County, New Mexico |
| Formation(s) (if applicable): | Wolfcamp |
| Bond Coverage: | \$25,000 statewide bond of Murchison Oil & Gas, Inc. |
| BLM Bond File No: | Personal Statewide Bond NM 2163 |

Date

1/22/10

Arnold Nall

VP, Operations

Murchison Oil & Gas Inc.

DISTRICT I
1625 N. FRENCH DR., HOBBS, NM 88240

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised October 12, 2005
Submit to Appropriate District Office
State Lease - 4 Copies
Fee Lease - 3 Copies

DISTRICT II
1301 W. GRAND AVENUE, ARTESIA, NM 88210

OIL CONSERVATION DIVISION
1220 SOUTH ST. FRANCIS DR.
Santa Fe, New Mexico 87505

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410

DISTRICT IV
1220 S. ST. FRANCIS DR., SANTA FE, NM 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

| | | |
|---------------|------------------------------|----------------------|
| API Number | Pool Code | Pool Name |
| | | DOG CANYON; WOLFCAMP |
| Property Code | Property Name | Well Number |
| | CARBON VALLEY 26 FEDERAL COM | 1H |
| OGRID No. | Operator Name | Elevation |
| | MURCHISON OIL & GAS, INC. | 3491' |

Surface Location


| UL or lot No. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| I | 26 | 16--S | 27-E | | 1980 | SOUTH | 250 | EAST | EDDY |

Bottom Hole Location If Different From Surface

| UL or lot No. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| L | 26 | 16-S | 27-E | | 1980 | SOUTH | 330 | WEST | EDDY |

| Dedicated Acres | Joint or Infill | Consolidation Code | Order No. |
|-----------------|-----------------|--------------------|-----------|
| 160 | | | |

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



OPERATOR CERTIFICATION

I hereby certify that the information herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.


A. Arnold Nall 1/22/10
Signature Date
A. Arnold Nall
Printed Name

SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

DECEMBER 21, 2009
Date Surveyed LA REV: 1/22/10
Signature & Seal of Professional Surveyor
3239
10:13:0104
Certificate No. GARY EIDSON 12641
RONALD J. EIDSON 3239

LOCATION VERIFICATION MAP



SCALE: 1" = 2000'

CONTOUR INTERVAL:

ARTESIA NE, N.M. - 10'

DIAMOND MOUND, N.M. - 10'

SEC. 26 TWP. 16-S RGE. 27-E

SURVEY N.M.P.M.

COUNTY EDDY STATE NEW MEXICO

DESCRIPTION 1980' FSL & 250' FEL


ELEVATION 3491'

OPERATOR MURCHISON
OIL & GAS, INC.


LEASE CARBON VALLEY 26 FED. COM #1H

U.S.G.S. TOPOGRAPHIC MAP


ARTESIA NE, N.M.



VICINITY MAP




SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO



DIRECTIONS TO LOCATION

FROM THE INTERSECTION OF U.S. HWY. #82 AND CO. RD. #202, GO NORTH ON CO. RD. #202 APPROX. 3.0 MILES. VEER NORTHEAST AND GO APPROX. 1-2 MILES. VEER NORTHWEST AND GO APPROX. 2.2 MILES. TURN RIGHT AND GO NORTHEAST APPROX. 800 FEET. TURN NORTH AND GO APPROX. 1900 FEET. LOCATION STAKE IS APPROX. 200 FEET WEST.



MURCHISON OIL & GAS, INC.

CARBON VALLEY 26 FEDERAL COM #1H WELL
 LOCATED 1980 FEET FROM THE SOUTH LINE
 AND 250 FEET FROM THE EAST LINE OF SECTION 26,
 TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
 EDDY COUNTY, NEW MEXICO.

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 09.11.1320 | Dr By: LA |
| Date: 12/23/09 | 09111320 |
| | Scale: 1"=100' |





EXHIBIT E-2

SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



DESCRIPTION

A STRIP OF LAND 50.0 FEET WIDE AND 527.4 FEET OR 0.100 MILES IN LENGTH CROSSING USA LAND IN SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, NMPM, EDDY COUNTY, NEW MEXICO AND BEING 25.0 FEET LEFT AND 25.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

I HEREBY CERTIFY THAT I HAVE DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

1000 0 1000 2000 FEET
Scale: 1" = 1000'

MURCHISON OIL & GAS, INC.

SURVEY OF AN EXSTING ACCESS ROAD CROSSING
SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO


| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

Ronald J. Edson 1/22/2010
RONALD J. EDSON N.M. P.S. No. 3239

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117

EXHIBIT E-3

SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.




DESCRIPTION

A STRIP OF LAND 20.0 FEET WIDE CROSSING STATE OF NEW MEXICO LAND IN SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 10.0 FEET RIGHT AND 10.0 FEET LEFT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT ON THE NORTH LINE OF THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER OF SAID SECTION, WHICH LIES N02°09'42\"W 1347.4 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION; THEN S00°11'35\"E 827.0 FEET; THEN S00°11'45\"W 406.3 FEET; THEN S59°42'05\"W 75.1 FEET; THEN S78°18'30\"W 164.4 FEET; THEN S88°32'45\"W 213.9 FEET; THEN N73°58'53\"W 117.0 FEET; THEN N56°51'48\"W 187.1 FEET; S81°17'44\"W 125.2 FEET; THEN S34°30'34\"E 149.0 FEET TO A POINT ON THE SOUTH LINE OF SAID SECTION, WHICH LIES N87°53'04\"W 798.4 FEET FROM THE SOUTHEAST CORNER OF SAID SECTION.

SAID STRIP OF LAND BEING 2265.0 FEET OR 137.27 RODS IN LENGTH, CONTAINING 1.040 ACRES MORE OR LESS AND BEING ENTIRELY LOCATED IN THE SOUTHEAST QUARTER OF THE SOUTHEAST QUARTER.

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM \"NEW MEXICO EAST ZONE\" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.



I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

Ronald J. Elson 01/22/2010
RONALD J. ELSON N.M. P.S. No. 3239

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117


MURCHISON OIL & GAS, INC.

SURVEY OF AN EXISTING ACCESS ROAD CROSSING
SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

EXHIBIT E-4

SECTION 35, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.




DESCRIPTION

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING SECTION 35, TOWNSHIP 16 SOUTH, RANGE 27 EAST, NMPM, EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE NORTH LINE OF SAID SECTION WHICH LIES N87°53'04\"W 798.4 FEET FROM THE NORTHEAST CORNER OF SAID SECTION; THEN S34°30'34\"E 279.3 FEET; THEN S33°30'25\"E 626.4 FEET; THEN S36°06'11\"E 643.8 FEET TO A POINT ON THE EAST LINE OF SAID SECTION WHICH LIES S03°56'04\"E 1246.0 FEET FROM THE NORTHEAST CORNER OF SAID SECTION.


TOTAL LENGTH EQUALS 1549.5 FEET OR 93.91 RODS

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM \"NEW MEXICO EAST ZONE\" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.



I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

Ronald J. Eidson 01/22/2010
RONALD J. EIDSON N.M. P.S. No. 3239




MURCHISON OIL & GAS, INC.

SURVEY OF AN EXISTING ACCESS ROAD CROSSING SECTION 35, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

EXHIBIT E-5

SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.




DESCRIPTION

CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST, NMPM, EDDY COUNTY, NEW MEXICO AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT A POINT ON THE WEST LINE OF SAID SECTION WHICH LIES S03°56'04\"E 1246.0 FEET FROM THE NORTHWEST CORNER OF SAID SECTION; THEN S36°06'11\"E 648.0 FEET; THEN S35°10'41\"E 1179.1 FEET TO A POINT ON THE SOUTH LINE OF THE NORTHWEST QUARTER OF SAID SECTION WHICH LIES S87°33'13\"E 962.5 FEET FROM THE WEST QUARTER CORNER OF SAID SECTION.

TOTAL LENGTH EQUALS 1827.1 FEET OR 110.73 RODS

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.



I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

Ronald J. Edson 01/22/2010
RONALD J. EDSON N.M. P.S. No. 3239

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117


MURCHISON OIL & GAS, INC.

SURVEY OF AN EXISTING ACCESS ROAD CROSSING
SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

EXHIBIT E-6

SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



DESCRIPTION

A STRIP OF LAND 20.0 FEET WIDE CROSSING STATE OF NEW MEXICO LAND IN SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M., EDDY COUNTY, NEW MEXICO AND BEING 10.0 FEET RIGHT AND 10.0 FEET LEFT OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT ON THE NORTH LINE OF THE SOUTH HALF OF SAID SECTION, WHICH LIES S87°33'13"E 962.5 FEET FROM THE WEST QUARTER CORNER OF SAID SECTION; THEN S35°10'41"E 2467.9 FEET; THEN S33°39'38"E 919.8 FEET TO A POINT ON THE SOUTH LINE OF SAID SECTION, WHICH LIES S87°12'27"E 280.8 FEET FROM THE SOUTH QUARTER CORNER OF SAID SECTION.

SAID STRIP OF LAND BEING 3387.7 FEET OR 205.32 RODS IN LENGTH, CONTAINING 1.555 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NW/4 SW/4 34.21 RODS OR 0.259 ACRES
NE/4 SW/4 68.80 RODS OR 0.521 ACRES
SE/4 SW/4 70.19 RODS OR 0.532 ACRES
SW/4 SE/4 32.12 RODS OR 0.243 ACRES

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

Ronald J. Elison 01/22/2010
RONALD J. ELISON N.M. P.S. No. 3239

PROVIDING SURVEYING SERVICES
SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117

1000 0 1000 2000 FEET
Scale: 1"=1000'


MURCHISON OIL & GAS, INC.

SURVEY OF AN EXISTING ACCESS ROAD CROSSING
SECTION 36, TOWNSHIP 16 SOUTH, RANGE 27 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

EXHIBIT E-7

SECTION 1, TOWNSHIP 17 SOUTH, RANGE 27 EAST, N.M.P.M.,
SECTION 6, TOWNSHIP 17 SOUTH, RANGE 28 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



DESCRIPTION

A STRIP OF LAND 50.0 FEET WIDE AND 5158.1 FEET OR 0.977 MILES IN LENGTH CROSSING USA LAND IN SECTION 1, TOWNSHIP 17 SOUTH, RANGE 27 EAST & SECTION 6, TOWNSHIP 17 SOUTH, RANGE 28 EAST, NMPM, EDDY COUNTY, NEW MEXICO AND BEING 25.0 FEET LEFT AND 25.0 FEET RIGHT OF THE ABOVE PLATTED CENTERLINE SURVEY.

NOTE: BEARINGS SHOWN HEREON ARE MERCATOR GRID AND CONFORM TO THE NEW MEXICO COORDINATE SYSTEM "NEW MEXICO EAST ZONE" NORTH AMERICAN DATUM 1983. DISTANCES ARE SURFACE VALUES.

I HEREBY CERTIFY THAT I DIRECTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR SURVEYING IN NEW MEXICO.

1000 0 1000 2000 FEET
Scale: 1"=1000'

MURCHISON OIL & GAS, INC.


SURVEY OF AN EXISTING ACCESS ROAD CROSSING SECTION 1, TOWNSHIP 17 SOUTH, RANGE 27 EAST & SECTION 6, TOWNSHIP 17 SOUTH, RANGE 28 EAST, NMPM, EDDY COUNTY, NEW MEXICO


| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Drawn By: LA |
| Date: 1/22/10 | 10130104 |

Ronald J. Eason 01/22/2010
RONALD J. EASON N.M. P.S. No. 3239

PROVIDING SURVEYING SERVICES SINCE 1946
JOHN WEST SURVEYING COMPANY
412 N. DAL PASO
HOBBS, N.M. 88240
(575) 393-3117

EXHIBIT C-1





ATTACHMENT TO FORM 3160-3
Murchison Oil & Gas, Inc.
Carbon Valley 26 Fed Com #1-H
SL: 1980' FSL & 250' FEL, UNIT I
BHL: 1980' FSL & 330' FWL, UNIT L
Sec 26, T16S, R27E
Eddy County, New Mexico

1. Proration Unit Spacing: 160 acres
2. Ground Elevation: 3491' Est. RKB 3510'

3. ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS

| | <u>DEPTH (RKB)</u> | <u>SUBSURFACE</u> |
|------------|--------------------|-------------------|
| Queen | 723' | +2787' |
| Premier | 1475' | +2035' |
| San Andres | 1535' | +1975' |
| Glorietta | 2960' | +550' |
| Yeso | 3055' | +455' |
| Tubb | 4275' | -765' |
| Abo | 5264' | -1754' |
| Wolfcamp | 6234' | -2724' |

*Pilot Hole – True Vertical Depth 6500' -2990'

PROPOSED DEPTHS: TVD 6235' and MD 10705'

4. ESTIMATED DEPTHS OF ANTICIPATED FRESH WATER, OIL, OR GAS

| | | |
|-------------|-------------|----------------------------|
| Fresh Water | 195' – 215' | Seven Rivers Carbonate |
| Fresh Water | 370' – 395' | Bowers Sand (Seven Rivers) |
| Oil/Gas | 1535' | San Andres |
| Oil/Gas | 2960' | Glorietta |
| Oil/Gas | 4275' | Tubb |
| Oil/Gas | 5264' | Abo |
| Oil/Gas | 6234' | Wolfcamp |

5. CASING AND CEMENTING PROGRAM

| Casing Size | Hole Size | From To | Weight | Grade | Joint | Conditions |
|-------------|-----------|----------------|--------|---------|-------|------------|
| 9-5/8" | 12-1/4" | 0' – 1000' | 36.0# | J-55 | ST&C | New |
| 7" | 8-3/4" | 0' – 5700' | 26.0# | HCP-110 | LT&C | New |
| 4-1/2" | 6-1/8" | 5600' – 10705' | 11.6# | HCP-110 | BT&C | New |
| | | | | | | |

| Casing Size | Burst Rating, psi | Safety Factor | Collapse Rating, psi | Safety Factor | Tension Rating, 1000 lbs. | Safety Factor |
|-------------|-------------------|---------------|----------------------|---------------|---------------------------|---------------|
| 9-5/8" | 3520 | 1.25 | 2020 | 3.90 | 394 | 9.95 |
| 7" | 9950 | 3.10 | 7800 | 2.60 | 693 | 4.70 |
| 4-1/2" | 10690 | 3.20 | 8650 | 2.60 | 367 | 30+ |
| | | | | | | |

Equivalent or adequate grades and weights of casing may be substituted at time casing is run, depending on availability.

Attachment to Form 3160-3
Murchison Oil & Gas, Inc.
Carbon Valley 26 Fed Com #1-H
Page 2 of 3

6. CASING DEPTH AND CEMENTING PROGRAM:

9.625" Surface Casing - Cementing Program

Cement lead with 150 sacks of Interfill Class C + additives with yield = 2.45 cu.ft./sack, tail with 175 sacks Premium Plus + additives with yield = 1.34 cu.ft./sack; sufficient volume of cement will be pumped to ensure cement is circulated to surface.

7" Intermediate Casing and Fiberglass Tubing - Cementing Program

Cement lead with 300 sacks of Interfill Class H + additives with yield = 2.77 cu.ft./sack, tail with 300 sacks Super Class H + additives with yield = 1.61 cu.ft./sack; sufficient volume of cement will be pumped to ensure cement is circulated to surface. Will cement below 7" casing via 2-7/8" fiberglass tubing stinger to adequately plug back vertical pilot hole after logging and prior to drilling curve/horizontal section of well. May perform a 2-stage job utilizing DV tool if determined to be necessary to circulate cement to surface.

4.5" Production Casing - Cementing Program

Plan to utilize 4-1/2" 11.6# HCP-110 BTC Peak completion liner system from RSB packer @ 5600' to TD of 10705' MD. No cement required.

1000' – 10705' 11" 3000# ram type preventers with one set blind rams and one set pipe rams and a 3000# annular type preventer. A choke manifold and 120 gallon accumulator with floor and remote operating stations and auxiliary power system. Rotating head below 5500'. See attached Sketch of BOP Equipment.

A Kelly cock will be installed and maintained in operable condition and a drill string safety valve in the open position will be available on the rig floor.

After setting the 9 5/8" casing, the blowout preventers and related control equipment shall be pressure tested to 3000 psi and 1500 psi respectively. Any equipment failing to test satisfactorily shall be repaired or replaced. Results of the BOP test will be recorded in the Driller's Log.

The BOP's will be maintained ready for use until drilling operations are completed. Pipe and blind rams shall be activated each trip. Annular preventer shall be functionally operated at least weekly.

BOP drills will be conducted as necessary to assure that equipment is operational and each crew is properly trained to carry out emergency duties.

Accumulator shall maintain a pressure capacity reserve at all times to provide for the close-open-close sequence of the blind and pipe rams of the hydraulic preventers.

7. MUD PROGRAM

| | |
|----------------|---|
| 0 – 1000' | Fresh water / native mud. Wt. 8.4 to 8.6 ppg, vis 28-34 sec, Lime for pH control. Paper for seepage. Lost circulation may be encountered. |
| 1000' – 6200' | Cut brine. Wt. 8.4 – 8.8 ppg, vis 28-29 sec, No control water loss, lime for pH control. |
| 6200' – 10705' | Mud up with XCD Polymer mud system. Wt. 9.0 – 9.5 ppg, Vis 32-40 sec, WL 8-10 cc. |

Attachment to Form 3160-3
Murchison Oil & Gas, Inc.
Carbon Valley 26 Fed Com #1-H
Page 3 of 3

Sufficient mud materials will be kept on location at all times in order to combat lost circulation, or unexpected kicks. In order to run open-hole logs and casing, the viscosity and water loss may have to be adjusted to meet these needs.


Mud system monitoring equipment with derrick floor indicators and visual / audio alarms shall be installed and operative prior to drilling into the Wolfcamp formation. This equipment will remain in use until the production casing is run and cemented. Monitoring equipment shall consist of the following:

- A recording pit level indicator.
- A pit volume totalizer.
- A flowline sensor.

9. TESTING, LOGGING AND CORING PROGRAM

- A. Testing program: None planned.
 - B. Mud logging program. Two man unit from 1000' to TD.
 - C. Electric logging program: CNL/LDT/CAL/GR, MSFL/HALS/GR.
 - D. Coring program: None planned.
10. No abnormal temperatures or pressures are anticipated. Low levels of H₂S have been monitored in producing wells in the area, so H₂S may be present while drilling the well. An H₂S Plan is attached to the Drilling Program. Anticipated Bottom Hole Pressure is 2700 PSI (maximum), and anticipated static Bottom Hole Temperature is 125 degrees Fahrenheit.
11. Anticipated starting date is April 1, 2010. It should take approximately 30 days to drill the well and another 10-15 days to complete.
12. A statement accepting responsibility for operations is attached.
13. The Multi-Point Surface Use & Operation Plan is attached.
14. If the Bureau of Land Management needs additional information to evaluate this application, please advise.



Murchison Oil & Gas



Project: Eddy County (NAD27)
Site: Carbon Valley 26 Federal Com
Well: #1H
Wellbore: OH
Plan: Plan #1 (#1H/OH)

| WELL DETAILS: #1H | | | | | | | | | |
|---|-----------|------------|--------|------------|---------|------------------|-------|-------------------|-------------|
| Ground Elevation: 3491.00 | | | | | | | | | |
| RKB Elevation: WELL @ 3505.00ft (18" KB Correction) | | | | | | | | | |
| Rig Name: 18" KB Correction | | | | | | | | | |
| | | Northing | | Easting | | Latitude | | Longitude | |
| +N/S | | 687985.700 | | 528246.100 | | 32° 53' 28.550 N | | 104° 14' 28.731 W | |
| +E/W | | 0.00 | | 0.00 | | 0.00 | | 0.00 | |
| SECTION DETAILS | | | | | | | | | |
| Sec | MD | Inc | Azi | TVD | +N/S | +E/W | DLag | TFace | VSec Target |
| 1 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 2 | 5757.50 | 0.00 | 0.00 | 5757.50 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 3 | 6516.00 | 91.00 | 272.04 | 6235.00 | 17.30 | -485.60 | 12.00 | 272.04 | 485.51 |
| 4 | 6540.31 | 91.00 | 272.04 | 6234.58 | 18.16 | -509.89 | 0.01 | 91.24 | 510.21 |
| 5 | -10705.90 | 91.00 | 272.04 | 6234.58 | -166.60 | -4672.20 | 0.00 | 0.00 | 4672.52 |
| WELLBORE TARGET DETAILS (MAP CO-ORDINATES) | | | | | | | | | |
| Name | | TVD | | +N/S | | +E/W | | Northing | |
| PBHL(CV26) | | 6161.88 | | 166.60 | | -4672.20 | | 688132.300 | |
| | | | | | | | | Easting | |
| | | | | | | | | Shape Point | |
| | | | | | | | | 523573.900 | |

West(-)/East(+) (200 ft/in)



PROJECT DETAILS: Eddy County (NAD27)
Geodetic System: US State Plane 1927 (Exact solution)
Datum: NAD 1927 (NADCON CONUS)
Ellipsoid: Clarke 1866
Zone: New Mexico East 3001
System Datum: Mean Sea Level
Local North: Grid

Murchison Oil & Gas

Eddy County (NAD27)
Carbon Valley 26 Federal Com
#1H
OH

Plan: Plan #1

Pathfinder X & Y Planning Report

12 January, 2010

The logo for Pathfinder, featuring the word "PATHFINDER" in a bold, sans-serif font. The "PATH" is in a light purple color, and "FINDER" is in a dark purple color. A green swoosh underline is positioned beneath the "FINDER" portion of the text.

| | | | |
|------------------|------------------------------|-------------------------------------|--------------------------------------|
| Company: | Murchison Oil & Gas | Local Co-ordinate Reference: | Well #1H |
| Project: | Eddy County (NAD27) | TVD Reference: | WELL @ 3509.00ft (18' KB Correction) |
| Site: | Carbon Valley 26 Federal Com | MD Reference: | WELL @ 3509.00ft (18' KB Correction) |
| Well: | #1H | North Reference: | Grid |
| Wellbore: | OH | Survey Calculation Method: | Minimum Curvature |
| Design: | Plan #1 | Database: | Midland Database |

| | | | |
|--------------------|--------------------------------------|----------------------|----------------|
| Project | Eddy County (NAD27) | System Datum: | Mean Sea Level |
| Map System: | US State Plane 1927 (Exact solution) | | |
| Geo Datum: | NAD 1927 (NADCON CONUS) | | |
| Map Zone: | New Mexico East 3001 | | |

| | | | |
|------------------------------|------------------------------|---------------------------------|-------------------------------------|
| Site | Carbon Valley 26 Federal Com | | |
| Site Position: | | | |
| From: | Map | Northing: 687,965.700 ft | Latitude: 32° 53' 28.550 N |
| Position Uncertainty: | 0.00 ft | Easting: 528,246.100 ft | Longitude: 104° 14' 28.731 W |
| | | Slot Radius: " | Grid Convergence: 0.05 ° |

| | | | |
|-----------------------------|---------|---------------------------------|-------------------------------------|
| Well | #1H | | |
| Well Position | | | |
| +N/-S | 0.00 ft | Northing: 687,965.700 ft | Latitude: 32° 53' 28.550 N |
| +E/-W | 0.00 ft | Easting: 528,246.100 ft | Longitude: 104° 14' 28.731 W |
| Position Uncertainty | 0.00 ft | Wellhead Elevation: ft | Ground Level: 3,491.00 ft |

| | | | |
|-------------------|----------|----------------------------|------------|
| Wellbore | OH | | |
| Magnetics | | | |
| Model Name | IGRF2010 | Sample Date | 01/08/2010 |
| | | Declination (°) | 8.12 |
| | | Dip Angle (°) | 60.72 |
| | | Field Strength (nT) | 49,084 |

| | | | |
|--------------------------|------------------------------|----------------------|---------------------------|
| Design | Plan #1 | | |
| Audit Notes: | | | |
| Version: | | Phase: PLAN | Tie On Depth: 0.00 |
| Vertical Section: | | | |
| | Depth From (TVD) (ft) | +N/-S (ft) | +E/-W (ft) |
| | 0.00 | 0.00 | 0.00 |
| | | Direction (°) | 272.04 |

| | | | |
|----------------------------|----------------|--------------------------|------------------|
| Survey Tool Program | Date | 01/12/2010 | |
| From (ft) | To (ft) | Survey (Wellbore) | Tool Name |
| 0.00 | 10,705.90 | Plan #1 (OH) | MWD |
| | | | MWD - Standard |

Pathfinder Energy Services

Pathfinder X & Y Planning Report



Company: Murchison Oil & Gas
Project: Eddy County (NAD27)
Site: Carbon Valley 26 Federal Com
Well: #1H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Database:

Well #1H
 WELL @ 3509.00ft (18' KB Correction)
 WELL @ 3509.00ft (18' KB Correction)
 Grid
 Minimum Curvature
 Midland Database

Planned Survey

| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDSS (ft) | N/S (ft) | E/W (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
|------------|------------|------------|-------------|---------------|-------------|-------------|----------------|-------------------|------------------|-----------------|
| 0.00 | 0.00 | 0.00 | 0.00 | -3,509.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 100.00 | 0.00 | 0.00 | 100.00 | -3,409.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 200.00 | 0.00 | 0.00 | 200.00 | -3,309.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 300.00 | 0.00 | 0.00 | 300.00 | -3,209.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 400.00 | 0.00 | 0.00 | 400.00 | -3,109.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 500.00 | 0.00 | 0.00 | 500.00 | -3,009.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 600.00 | 0.00 | 0.00 | 600.00 | -2,909.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 700.00 | 0.00 | 0.00 | 700.00 | -2,809.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 800.00 | 0.00 | 0.00 | 800.00 | -2,709.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 900.00 | 0.00 | 0.00 | 900.00 | -2,609.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,000.00 | 0.00 | 0.00 | 1,000.00 | -2,509.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,100.00 | 0.00 | 0.00 | 1,100.00 | -2,409.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,200.00 | 0.00 | 0.00 | 1,200.00 | -2,309.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,300.00 | 0.00 | 0.00 | 1,300.00 | -2,209.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,400.00 | 0.00 | 0.00 | 1,400.00 | -2,109.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,500.00 | 0.00 | 0.00 | 1,500.00 | -2,009.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,600.00 | 0.00 | 0.00 | 1,600.00 | -1,909.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,700.00 | 0.00 | 0.00 | 1,700.00 | -1,809.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,800.00 | 0.00 | 0.00 | 1,800.00 | -1,709.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 1,900.00 | 0.00 | 0.00 | 1,900.00 | -1,609.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,000.00 | 0.00 | 0.00 | 2,000.00 | -1,509.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,100.00 | 0.00 | 0.00 | 2,100.00 | -1,409.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,200.00 | 0.00 | 0.00 | 2,200.00 | -1,309.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,300.00 | 0.00 | 0.00 | 2,300.00 | -1,209.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,400.00 | 0.00 | 0.00 | 2,400.00 | -1,109.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,500.00 | 0.00 | 0.00 | 2,500.00 | -1,009.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,600.00 | 0.00 | 0.00 | 2,600.00 | -909.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |

Pathfinder Energy Services

Pathfinder X & Y Planning Report



Company: Murchison Oil & Gas
Project: Eddy County (NAD27)
Site: Carbon Valley 26 Federal Com
Well: #1H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Database:

Well #1H
WELL @ 3509.00ft (18' KB Correction)
WELL @ 3509.00ft (18' KB Correction)
Grid
Minimum Curvature
Midland Database

Planned Survey

| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDSS (ft) | N/S (ft) | E/W (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
|------------|------------|------------|-------------|---------------|-------------|-------------|----------------|-------------------|------------------|-----------------|
| 2,700.00 | 0.00 | 0.00 | 2,700.00 | -809.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,800.00 | 0.00 | 0.00 | 2,800.00 | -709.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 2,900.00 | 0.00 | 0.00 | 2,900.00 | -609.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,000.00 | 0.00 | 0.00 | 3,000.00 | -509.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,100.00 | 0.00 | 0.00 | 3,100.00 | -409.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,200.00 | 0.00 | 0.00 | 3,200.00 | -309.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,300.00 | 0.00 | 0.00 | 3,300.00 | -209.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,400.00 | 0.00 | 0.00 | 3,400.00 | -109.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,500.00 | 0.00 | 0.00 | 3,500.00 | -9.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,600.00 | 0.00 | 0.00 | 3,600.00 | 91.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,700.00 | 0.00 | 0.00 | 3,700.00 | 191.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,800.00 | 0.00 | 0.00 | 3,800.00 | 291.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 3,900.00 | 0.00 | 0.00 | 3,900.00 | 391.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,000.00 | 0.00 | 0.00 | 4,000.00 | 491.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,100.00 | 0.00 | 0.00 | 4,100.00 | 591.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,200.00 | 0.00 | 0.00 | 4,200.00 | 691.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,300.00 | 0.00 | 0.00 | 4,300.00 | 791.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,400.00 | 0.00 | 0.00 | 4,400.00 | 891.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,500.00 | 0.00 | 0.00 | 4,500.00 | 991.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,600.00 | 0.00 | 0.00 | 4,600.00 | 1,091.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,700.00 | 0.00 | 0.00 | 4,700.00 | 1,191.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,800.00 | 0.00 | 0.00 | 4,800.00 | 1,291.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 4,900.00 | 0.00 | 0.00 | 4,900.00 | 1,391.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,000.00 | 0.00 | 0.00 | 5,000.00 | 1,491.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,100.00 | 0.00 | 0.00 | 5,100.00 | 1,591.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,200.00 | 0.00 | 0.00 | 5,200.00 | 1,691.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,300.00 | 0.00 | 0.00 | 5,300.00 | 1,791.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |

Pathfinder Energy Services

Pathfinder X & Y Planning Report



Company: Murchison Oil & Gas
Project: Eddy County (NAD27)
Site: Carbon Valley 26 Federal Com
Well: #1H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Database:

Well #1 H
 WELL @ 3509.00ft (18' KB Correction)
 WELL @ 3509.00ft (18' KB Correction)
 Grid
 Minimum Curvature
 Midland Database

Planned Survey

| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDSS (ft) | N/S (ft) | E/W (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
|---|------------|------------|-------------|---------------|-------------|-------------|----------------|-------------------|------------------|-----------------|
| 5,400.00 | 0.00 | 0.00 | 5,400.00 | 1,891.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,500.00 | 0.00 | 0.00 | 5,500.00 | 1,991.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,600.00 | 0.00 | 0.00 | 5,600.00 | 2,091.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,700.00 | 0.00 | 0.00 | 5,700.00 | 2,191.00 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| 5,757.50 | 0.00 | 0.00 | 5,757.50 | 2,248.50 | 0.00 | 0.00 | 0.00 | 0.00 | 687,965.70 | 528,246.10 |
| KOP-5757.50*MD,0.00*INC,0.00*AZI,5757.50*TVD | | | | | | | | | | |
| 5,775.00 | 2.10 | 272.04 | 5,775.00 | 2,266.00 | 0.01 | -0.32 | 0.32 | 12.00 | 687,965.71 | 528,245.78 |
| 5,800.00 | 5.10 | 272.04 | 5,799.94 | 2,290.94 | 0.07 | -1.89 | 1.89 | 12.00 | 687,965.77 | 528,244.21 |
| 5,825.00 | 8.10 | 272.04 | 5,824.78 | 2,315.78 | 0.17 | -4.76 | 4.76 | 12.00 | 687,965.87 | 528,241.34 |
| 5,850.00 | 11.10 | 272.04 | 5,849.42 | 2,340.42 | 0.32 | -8.92 | 8.93 | 12.00 | 687,966.02 | 528,237.18 |
| 5,875.00 | 14.10 | 272.04 | 5,873.82 | 2,364.82 | 0.51 | -14.37 | 14.38 | 12.00 | 687,966.21 | 528,231.73 |
| 5,900.00 | 17.10 | 272.04 | 5,897.89 | 2,388.89 | 0.75 | -21.09 | 21.10 | 12.00 | 687,966.45 | 528,225.01 |
| 5,925.00 | 20.10 | 272.04 | 5,921.59 | 2,412.59 | 1.03 | -29.06 | 29.07 | 12.00 | 687,966.73 | 528,217.04 |
| 5,950.00 | 23.09 | 272.04 | 5,944.83 | 2,435.83 | 1.36 | -38.25 | 38.27 | 12.00 | 687,967.06 | 528,207.85 |
| 5,975.00 | 26.09 | 272.04 | 5,967.56 | 2,458.56 | 1.73 | -48.65 | 48.68 | 12.00 | 687,967.43 | 528,197.45 |
| 6,000.00 | 29.09 | 272.04 | 5,989.71 | 2,480.71 | 2.14 | -60.22 | 60.26 | 12.00 | 687,967.84 | 528,185.88 |
| 6,025.00 | 32.09 | 272.04 | 6,011.23 | 2,502.23 | 2.60 | -72.93 | 72.98 | 12.00 | 687,968.30 | 528,173.17 |
| 6,050.00 | 35.09 | 272.04 | 6,032.05 | 2,523.05 | 3.09 | -86.75 | 86.81 | 12.00 | 687,968.79 | 528,159.35 |
| 6,075.00 | 38.09 | 272.04 | 6,052.12 | 2,543.12 | 3.62 | -101.65 | 101.71 | 12.00 | 687,969.32 | 528,144.45 |
| 6,100.00 | 41.09 | 272.04 | 6,071.39 | 2,562.39 | 4.19 | -117.57 | 117.64 | 12.00 | 687,969.89 | 528,128.53 |
| 6,125.00 | 44.09 | 272.04 | 6,089.79 | 2,580.79 | 4.79 | -134.47 | 134.56 | 12.00 | 687,970.49 | 528,111.63 |
| 6,150.00 | 47.09 | 272.04 | 6,107.28 | 2,598.28 | 5.43 | -152.32 | 152.41 | 12.00 | 687,971.13 | 528,093.78 |
| 6,175.00 | 50.09 | 272.04 | 6,123.82 | 2,614.82 | 6.09 | -171.05 | 171.16 | 12.00 | 687,971.79 | 528,075.05 |
| 6,200.00 | 53.09 | 272.04 | 6,139.35 | 2,630.35 | 6.79 | -190.63 | 190.75 | 12.00 | 687,972.49 | 528,055.47 |
| 6,225.00 | 56.09 | 272.04 | 6,153.83 | 2,644.83 | 7.52 | -210.99 | 211.12 | 12.00 | 687,973.22 | 528,035.11 |
| 6,250.00 | 59.09 | 272.04 | 6,167.23 | 2,658.23 | 8.27 | -232.08 | 232.22 | 12.00 | 687,973.97 | 528,014.02 |
| 6,275.00 | 62.09 | 272.04 | 6,179.51 | 2,670.51 | 9.04 | -253.84 | 254.00 | 12.00 | 687,974.74 | 527,992.26 |

Pathfinder Energy Services

Pathfinder X & Y Planning Report



Company: Murchison Oil & Gas
 Project: Eddy County (NAD27)
 Site: Carbon Valley 26 Federal Com
 Well: #1H
 Wellbore: OH
 Design: Plan #1

Local Co-ordinate Reference:
 TVD Reference:
 MD Reference:
 North Reference:
 Survey Calculation Method:
 Database:

Well #1H
 WELL @ 3509.00ft (18' KB Correction)
 WELL @ 3509.00ft (18' KB Correction)
 Grid
 Minimum Curvature
 Midland Database

Planned Survey

| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDS (ft) | N/S (ft) | EW (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
|--|------------|------------|-------------|--------------|-------------|------------|----------------|-------------------|------------------|-----------------|
| 6,300.00 | 65.09 | 272.04 | 6,190.63 | 2,681.63 | 9.84 | -276.21 | 276.39 | 12.00 | 687,975.54 | 527,969.89 |
| 6,325.00 | 68.08 | 272.04 | 6,200.56 | 2,691.56 | 10.66 | -299.14 | 299.32 | 12.00 | 687,976.36 | 527,946.96 |
| 6,350.00 | 71.08 | 272.04 | 6,209.28 | 2,700.28 | 11.49 | -322.55 | 322.75 | 12.00 | 687,977.19 | 527,923.55 |
| 6,375.00 | 74.08 | 272.04 | 6,216.76 | 2,707.76 | 12.34 | -346.38 | 346.60 | 12.00 | 687,978.04 | 527,899.72 |
| 6,400.00 | 77.08 | 272.04 | 6,222.99 | 2,713.99 | 13.20 | -370.58 | 370.81 | 12.00 | 687,978.90 | 527,875.52 |
| 6,425.00 | 80.08 | 272.04 | 6,227.94 | 2,718.94 | 14.07 | -395.06 | 395.32 | 12.00 | 687,979.77 | 527,851.04 |
| 6,450.00 | 83.08 | 272.04 | 6,231.60 | 2,722.60 | 14.95 | -419.78 | 420.04 | 12.00 | 687,980.65 | 527,826.32 |
| 6,475.00 | 86.08 | 272.04 | 6,233.96 | 2,724.96 | 15.84 | -444.65 | 444.93 | 12.00 | 687,981.54 | 527,801.45 |
| 6,500.00 | 89.08 | 272.04 | 6,235.01 | 2,726.01 | 16.73 | -469.61 | 469.90 | 12.00 | 687,982.43 | 527,776.49 |
| 6,516.00 | 91.00 | 272.04 | 6,235.00 | 2,726.00 | 17.30 | -485.60 | 485.91 | 12.00 | 687,983.00 | 527,760.50 |
| EOC-6516.00°MD,91.00°INC,272.20°AZI,6235.00°TVD,12.00°DLS, 485.90°VS, 18.65°N, -485.54°E | | | | | | | | | | |
| 6,540.31 | 91.00 | 272.04 | 6,234.58 | 2,725.58 | 18.16 | -509.89 | 510.21 | 0.01 | 687,983.86 | 527,736.21 |
| 6,600.00 | 91.00 | 272.04 | 6,233.53 | 2,724.53 | 20.29 | -569.53 | 569.89 | 0.00 | 687,985.99 | 527,676.57 |
| 6,700.00 | 91.00 | 272.04 | 6,231.79 | 2,722.79 | 23.85 | -669.45 | 669.87 | 0.00 | 687,989.55 | 527,576.65 |
| 6,800.00 | 91.00 | 272.04 | 6,230.04 | 2,721.04 | 27.42 | -769.37 | 769.86 | 0.00 | 687,993.12 | 527,476.73 |
| 6,900.00 | 91.00 | 272.04 | 6,228.30 | 2,719.30 | 30.98 | -869.29 | 869.84 | 0.00 | 687,996.68 | 527,376.81 |
| 7,000.00 | 91.00 | 272.04 | 6,226.55 | 2,717.55 | 34.54 | -969.21 | 969.83 | 0.00 | 688,000.24 | 527,276.89 |
| 7,100.00 | 91.00 | 272.04 | 6,224.81 | 2,715.81 | 38.11 | -1,069.13 | 1,069.81 | 0.00 | 688,003.81 | 527,176.97 |
| 7,200.00 | 91.00 | 272.04 | 6,223.06 | 2,714.06 | 41.67 | -1,169.06 | 1,169.80 | 0.00 | 688,007.37 | 527,077.04 |
| 7,300.00 | 91.00 | 272.04 | 6,221.32 | 2,712.32 | 45.23 | -1,268.98 | 1,269.78 | 0.00 | 688,010.93 | 526,977.12 |
| 7,400.00 | 91.00 | 272.04 | 6,219.57 | 2,710.57 | 48.80 | -1,368.90 | 1,369.77 | 0.00 | 688,014.50 | 526,877.20 |
| 7,500.00 | 91.00 | 272.04 | 6,217.83 | 2,708.83 | 52.36 | -1,468.82 | 1,469.75 | 0.00 | 688,018.06 | 526,777.28 |
| 7,600.00 | 91.00 | 272.04 | 6,216.08 | 2,707.08 | 55.92 | -1,568.74 | 1,569.74 | 0.00 | 688,021.62 | 526,677.36 |
| 7,700.00 | 91.00 | 272.04 | 6,214.34 | 2,705.34 | 59.49 | -1,668.66 | 1,669.72 | 0.00 | 688,025.19 | 526,577.44 |
| 7,800.00 | 91.00 | 272.04 | 6,212.59 | 2,703.59 | 63.05 | -1,768.58 | 1,769.71 | 0.00 | 688,028.75 | 526,477.52 |
| 7,900.00 | 91.00 | 272.04 | 6,210.85 | 2,701.85 | 66.61 | -1,868.50 | 1,869.69 | 0.00 | 688,032.31 | 526,377.60 |
| 8,000.00 | 91.00 | 272.04 | 6,209.10 | 2,700.10 | 70.18 | -1,968.43 | 1,969.68 | 0.00 | 688,035.88 | 526,277.67 |

Pathfinder Energy Services

Pathfinder X & Y Planning Report



Company: Murchison Oil & Gas
Project: Eddy County (NAD27)
Site: Carbon Valley 26 Federal Com
Well: #1H
Wellbore: OH
Design: Plan #1

Local Co-ordinate Reference:
TVD Reference:
MD Reference:
North Reference:
Survey Calculation Method:
Database:

Well #1H
WELL @ 3509.00ft (18' KB Correction)
WELL @ 3509.00ft (18' KB Correction)
Grid
Minimum Curvature
Midland Database

Planned Survey

| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDSS (ft) | N/S (ft) | E/W (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
|------------|------------|------------|-------------|---------------|-------------|-------------|----------------|-------------------|------------------|-----------------|
| 8,100.00 | 91.00 | 272.04 | 6,207.36 | 2,698.36 | 73.74 | -2,068.35 | 2,069.66 | 0.00 | 688,039.44 | 526,177.75 |
| 8,200.00 | 91.00 | 272.04 | 6,205.61 | 2,696.61 | 77.30 | -2,168.27 | 2,169.65 | 0.00 | 688,043.00 | 526,077.83 |
| 8,300.00 | 91.00 | 272.04 | 6,203.87 | 2,694.87 | 80.87 | -2,268.19 | 2,269.63 | 0.00 | 688,046.57 | 525,977.91 |
| 8,400.00 | 91.00 | 272.04 | 6,202.12 | 2,693.12 | 84.43 | -2,368.11 | 2,369.62 | 0.00 | 688,050.13 | 525,877.99 |
| 8,500.00 | 91.00 | 272.04 | 6,200.38 | 2,691.38 | 87.99 | -2,468.03 | 2,469.60 | 0.00 | 688,053.69 | 525,778.07 |
| 8,600.00 | 91.00 | 272.04 | 6,198.63 | 2,689.63 | 91.56 | -2,567.95 | 2,569.59 | 0.00 | 688,057.26 | 525,678.15 |
| 8,700.00 | 91.00 | 272.04 | 6,196.89 | 2,687.89 | 95.12 | -2,667.88 | 2,669.57 | 0.00 | 688,060.82 | 525,578.22 |
| 8,800.00 | 91.00 | 272.04 | 6,195.14 | 2,686.14 | 98.68 | -2,767.80 | 2,769.55 | 0.00 | 688,064.38 | 525,478.30 |
| 8,900.00 | 91.00 | 272.04 | 6,193.40 | 2,684.40 | 102.25 | -2,867.72 | 2,869.54 | 0.00 | 688,067.95 | 525,378.38 |
| 9,000.00 | 91.00 | 272.04 | 6,191.65 | 2,682.65 | 105.81 | -2,967.64 | 2,969.52 | 0.00 | 688,071.51 | 525,278.46 |
| 9,100.00 | 91.00 | 272.04 | 6,189.91 | 2,680.91 | 109.37 | -3,067.56 | 3,069.51 | 0.00 | 688,075.07 | 525,178.54 |
| 9,200.00 | 91.00 | 272.04 | 6,188.16 | 2,679.16 | 112.94 | -3,167.48 | 3,169.49 | 0.00 | 688,078.64 | 525,078.62 |
| 9,300.00 | 91.00 | 272.04 | 6,186.42 | 2,677.42 | 116.50 | -3,267.40 | 3,269.48 | 0.00 | 688,082.20 | 524,978.70 |
| 9,400.00 | 91.00 | 272.04 | 6,184.67 | 2,675.67 | 120.07 | -3,367.32 | 3,369.46 | 0.00 | 688,085.77 | 524,878.78 |
| 9,500.00 | 91.00 | 272.04 | 6,182.92 | 2,673.92 | 123.63 | -3,467.25 | 3,469.45 | 0.00 | 688,089.33 | 524,778.85 |
| 9,600.00 | 91.00 | 272.04 | 6,181.18 | 2,672.18 | 127.19 | -3,567.17 | 3,569.43 | 0.00 | 688,092.89 | 524,678.93 |
| 9,700.00 | 91.00 | 272.04 | 6,179.43 | 2,670.43 | 130.76 | -3,667.09 | 3,669.42 | 0.00 | 688,096.46 | 524,579.01 |
| 9,800.00 | 91.00 | 272.04 | 6,177.69 | 2,668.69 | 134.32 | -3,767.01 | 3,769.40 | 0.00 | 688,100.02 | 524,479.09 |
| 9,900.00 | 91.00 | 272.04 | 6,175.94 | 2,666.94 | 137.88 | -3,866.93 | 3,869.39 | 0.00 | 688,103.58 | 524,379.17 |
| 10,000.00 | 91.00 | 272.04 | 6,174.20 | 2,665.20 | 141.45 | -3,966.85 | 3,969.37 | 0.00 | 688,107.15 | 524,279.25 |
| 10,100.00 | 91.00 | 272.04 | 6,172.45 | 2,663.45 | 145.01 | -4,066.77 | 4,069.36 | 0.00 | 688,110.71 | 524,179.33 |
| 10,200.00 | 91.00 | 272.04 | 6,170.71 | 2,661.71 | 148.57 | -4,166.69 | 4,169.34 | 0.00 | 688,114.27 | 524,079.41 |
| 10,300.00 | 91.00 | 272.04 | 6,168.96 | 2,659.96 | 152.14 | -4,266.62 | 4,269.33 | 0.00 | 688,117.84 | 523,979.48 |
| 10,400.00 | 91.00 | 272.04 | 6,167.22 | 2,658.22 | 155.70 | -4,366.54 | 4,369.31 | 0.00 | 688,121.40 | 523,879.56 |
| 10,500.00 | 91.00 | 272.04 | 6,165.47 | 2,656.47 | 159.26 | -4,466.46 | 4,469.30 | 0.00 | 688,124.96 | 523,779.64 |
| 10,600.00 | 91.00 | 272.04 | 6,163.73 | 2,654.73 | 162.83 | -4,566.38 | 4,569.28 | 0.00 | 688,128.53 | 523,679.72 |

| | | | |
|------------------|------------------------------|-------------------------------------|--------------------------------------|
| Company: | Murchison Oil & Gas | Local Co-ordinate Reference: | Well #1H |
| Project: | Eddy County (NAD27) | TVD Reference: | WELL @ 3509.00ft (18' KB Correction) |
| Site: | Carbon Valley 26 Federal Com | MD Reference: | WELL @ 3509.00ft (18' KB Correction) |
| Well: | #1H | North Reference: | Grid |
| Wellbore: | OH | Survey Calculation Method: | Minimum Curvature |
| Design: | Plan #1 | Database: | Midland Database |

| Planned Survey | | | | | | | | | | |
|-----------------------------|------------|------------|-------------|---------------|-------------|-------------|----------------|-------------------|------------------|-----------------|
| MD (ft) | Inc (°) | Azi (°) | TVD (ft) | TVDSS (ft) | N/S (ft) | E/W (ft) | V. Sec (ft) | DLeg (°/100ft) | Northing (ft) | Easting (ft) |
| 10,705.90 | 91.00 | 272.04 | 6,161.88 | 2,652.88 | 166.60 | -4,672.20 | 4,675.16 | 0.00 | 688,132.30 | 523,573.90 |
| TD at 10705.90 - PBHL(CV26) | | | | | | | | | | |


| Targets | | | | | | | | | |
|---------------------------|------------------|-----------------|-------------|---------------|---------------|------------------|-----------------|------------------|-------------------|
| Target Name | Dip Angle (°) | Dip Dir. (°) | TVD (ft) | +N/-S (ft) | +E/-W (ft) | Northing (ft) | Easting (ft) | Latitude | Longitude |
| - hit/miss target | | | | | | | | | |
| - Shape | | | | | | | | | |
| PBHL(CV26) | 0.00 | 0.00 | 6,161.88 | 166.60 | -4,672.20 | 688,132.300 | 523,573.900 | 32° 53' 30.236 N | 104° 15' 23.525 W |
| - plan hits target center | | | | | | | | | |
| - Point | | | | | | | | | |

| Plan Annotations | | | | | |
|---------------------------|---------------------------|------------------------------------|---------------|---|--|
| Measured Depth (ft) | Vertical Depth (ft) | Local Coordinates +N/-S (ft) | +E/-W (ft) | Comment | |
| 5,757.50 | 5,757.50 | 0.00 | 0.00 | KOP-5757.50'MD,0.00°INC,0.00°AZI,5757.50'TVD | |
| 6,298.51 | 6,190.00 | 9.79 | -274.87 | Wolf Camp Pen. PT - 6298.51'MD,64.91°INC,272.20°AZI,6190.00'TVD | |
| 6,516.00 | 6,235.00 | 17.30 | -485.60 | EOC-6516.00'MD,91.00°INC,272.20°AZI,6235.00'TVD,12.00°DLS, 485 | |
| 10,705.90 | | | | TD at 10705.90 | |

Checked By: _____ Approved By: _____ Date: _____



EXHIBIT F

SECTION 26, TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



MURCHISON OIL & GAS, INC.
CARBON VALLEY 26 FEDERAL COM #1H
ELEV. 3491'

GEODETIC COORDINATES
NAD 27 NME
Y=687965.7 N
X=528246.1 E
LAT.=32.891264° N
LONG.=104.241314° W



MURCHISON OIL & GAS, INC.

CARBON VALLEY 26 FEDERAL COM #1H WELL
LOCATED 1980 FEET FROM THE SOUTH LINE
AND 250 FEET FROM THE EAST LINE OF SECTION 26,
TOWNSHIP 16 SOUTH, RANGE 27 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.

| | |
|-------------------------|---------------------|
| Survey Date: 12/21/09 | Sheet 1 of 1 Sheets |
| W.O. Number: 10.13.0104 | Dr By: LA |
| Date: 1/22/10 | 10130104 |
| | Scale: 1"=100' |

EXHIBIT G






EXHIBIT H

CHOKE MANIFOLD



Murchison Oil & Gas, Inc.

Closed Loop Equipment Diagram



District I
1625 N. French Dr., Hobbs, NM 88240
District II
1301 W. Grand Avenue, Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy Minerals and Natural Resources
Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-144 CLEZ
July 21, 2008

For closed-loop systems that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, submit to the appropriate NMOC District Office.

Closed-Loop System Permit or Closure Plan Application

(that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure)

Type of action: ☒ Permit ☐ Closure

Instructions: Please submit one application (Form C-144 CLEZ) per individual closed-loop system request. For any application request other than for a closed-loop system that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, please submit a Form C-144.

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.


1.
Operator: Murchison Oil & Gas, Inc. OGRID #: 015363
Address: 1100 Mira Vista Blvd., Plano, TX 75093-4698
Facility or well name: CARBON VALLEY 26 FED COM #1-H
API Number: 30-015- OCD Permit Number: _____
U/L or Qtr/Qtr I Section 26 Township 16S Range 27E County: Eddy
Center of Proposed Design: Latitude 32°89'12.64" Longitude 104°24'13.14" NAD: ☒ 1927 ☐ 1983
Surface Owner: ☒ Federal ☐ State ☐ Private ☐ Tribal Trust or Indian Allotment

2.
☒ **Closed-loop System:** Subsection H of 19.15.17.11 NMAC
Operation: ☒ Drilling a new well ☐ Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent) ☐ P&A
☐ Above Ground Steel Tanks or ☒ Haul-off Bins

3.
Signs: Subsection C of 19.15.17.11 NMAC
☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers
☒ Signed in compliance with 19.15.3.103 NMAC

4.
Closed-loop Systems Permit Application Attachment Checklist: Subsection B of 19.15.17.9 NMAC
Instructions: Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.
☒ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC
☒ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC
☒ Closure Plan (Please complete Box 5) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC
☐ Previously Approved Design (attach copy of design) API Number: _____
☐ Previously Approved Operating and Maintenance Plan API Number: _____

5.
Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only: (19.15.17.13.D NMAC)
Instructions: Please identify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required.
Disposal Facility Name: CRI Disposal Facility Permit Number: R9166
Disposal Facility Name: GMI Disposal Facility Permit Number: 711-019-001
Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future service and operations?
☐ Yes (If yes, please provide the information below) ☒ No
Required for impacted areas which will not be used for future service and operations:
☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

6.
Operator Application Certification:
I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.
Name (Print): A. Arnold Nall Title: VP Operations
Signature:  Date: 1/20/2010
e-mail address: arnall@jdmii.com Telephone: (972) 931-0700

7. **OCD Approval:** ☐ Permit Application (including closure plan) ☐ Closure Plan (only)

OCD Representative Signature: _____ Approval Date: _____

Title: _____ OCD Permit Number: _____

8.

Closure Report (required within 60 days of closure completion): Subsection K of 19.15.17.13 NMAC

Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.

☐ Closure Completion Date: _____

9.

Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:

Instructions: Please indentify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.

Disposal Facility Name: _____ Disposal Facility Permit Number: _____

Disposal Facility Name: _____ Disposal Facility Permit Number: _____

Were the closed-loop system operations and associated activities performed on or in areas that *will not* be used for future service and operations?

☐ Yes (If yes, please demonstrate compliance to the items below) ☐ No

Required for impacted areas which will not be used for future service and operations:

☐ Site Reclamation (Photo Documentation)

☐ Soil Backfilling and Cover Installation

☐ Re-vegetation Application Rates and Seeding Technique

10.

Operator Closure Certification:

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): _____ Title: _____

Signature: _____ Date: _____

e-mail address: _____ Telephone: _____

MURCHISON OIL & GAS, INC.

HYDROGEN SULFIDE (H₂S) CONTINGENCY PLAN FOR DRILLING/COMPLETING/WORKOVER/FACILITY WITH THE EXCEPTION OF H₂S IN EXCESS OF 100 PPM

**MURCHISON OIL & GAS, INC.
NEW DRILL WELL
CARBON VALLEY 26 FED COM #1-H
SL: 1980' FSL & 250' FEL, UNIT I
BHL: 1980' FSL & 330' FWL, UNIT L
SEC 26, T16S, R27E
EDDY COUNTY, NEW MEXICO**

This well/facility is not expected to have H₂S, but the following is submitted as requested.

TABLE OF CONTENTS

| | | |
|-------|---|---------|
| I. | General Emergency Plan | Page 3 |
| II. | Emergency Procedures for Uncontrolled Release of H ₂ S | Page 3 |
| III. | Emergency Call List | Page 3 |
| IV. | Emergency Response Numbers | Page 4 |
| V. | Protection of the General (ROE) Radius of Exposure | Page 4 |
| VI. | Public Evacuation Plan | Page 5 |
| VII. | Procedure for Igniting an Uncontrollable Condition | Page 5 |
| VIII. | Required Emergency Equipment | Page 6 |
| IX. | Using Self-Contained Breathing Air Equipment (SCBA) | Page 7 |
| X. | Rescue & First Aid for Victims of H ₂ S Poisoning | Page 7 |
| XI. | H ₂ S Toxic Effects | Pages 8 |
| XII. | H ₂ S Physical Properties | Pages 9 |
| XIII. | Location Map | Page 10 |
| XIV. | Vicinity Map | Page 11 |

GENERAL H2S EMERGENCY ACTIONS

In the event of any evidence of H2S emergency, the following plan will be initiated:

1. All personnel will immediately evacuate to an upwind and if possible uphill "safe area".
2. If for any reason a person must enter the hazardous area, they must wear a SCBA (self-contained breathing apparatus).
3. Always use the "buddy system."
4. Isolate the well/problem if possible.
5. Account for all personnel.
6. Display the proper colors warning all unsuspecting personnel of the danger at hand.
7. Contact the company representative as soon as possible if not at the location (use the enclosed call list as instructed).

At this point the company representative will evaluate the situation and coordinate the necessary duties to bring the situation under control, and if necessary, the notification of emergency response agencies and residents.

EMERGENCY PROCEDURES FOR AN UNCONTROLLABLE RELEASE OF H2S

1. All personnel will don the self-contained breathing apparatus.
2. Remove all personnel to the "safe area": (always use the "buddy system").
3. Contact company representative if not on location.
4. Set in motion the steps to protect and/or remove the general public to any upwind "safe area." Maintain strict security and safety procedures while dealing with the source.
5. No entry to any unauthorized personnel.
6. Notify the appropriate agencies:
City Police - City streets
State Police - State Roads
County Sheriff - County Roads
7. Call the NMOCD.

If at this time the supervising person determines the release of H2S cannot be contained to the site location and the general public is in harm's way, he will immediately notify public safety personnel.

EMERGENCY CALL LIST

| | <u>Office</u> | <u>Cell</u> | <u>Home</u> |
|--------------|---------------|--------------|--------------|
| Arnold Nall | 972-931-0700 | 214-415-3010 | 972-596-8504 |
| Tommy Folsom | 575-628-3932 | 575-706-0667 | 575-885-3474 |
| Randy Ford | 432-682-0440 | 432-599-2222 | 432-684-4334 |

EMERGENCY RESPONSE NUMBERS

Eddy County, New Mexico

| | |
|--|--------------|
| State Police | 888-442-6677 |
| Eddy County Sheriff - Carlsbad | 575-396-3611 |
| Eddy County Emergency Management - Carlsbad | 575-887-7551 |
| State Emergency Response Center (SERC) | 575-476-9620 |
| Artesia Police / Fire / Ambulance Department | 575-746-5000 |
| New Mexico Oil Conservation Division - Artesia | 575-748-1283 |
| Callaway Safety Equipment, Inc. | 575-392-2973 |

PROTECTION OF THE GENERAL (ROE) RADIUS OF EXPOSURE

In the event greater than 100 ppm H₂S is present, the ROE calculations will be done to determine if the following conditions exist and whether the Plan must be activated:

- * 100 ppm at any public area (any place not associated with this site)
- * 500 ppm at any public road (any road which the general public may travel).
- * 100 ppm radius of 3000' will be assumed if there is insufficient data to do the calculations, and there is a reasonable expectation that H₂S could be present in concentrations greater than 100 ppm in the gas mixture.

Calculation for the 100 ppm ROE: (H₂S concentrations in decimal form)

$$\text{ROE} = [(1.589)(\text{H}_2\text{S concentration})(Q)]^{(.6258)} \quad \begin{array}{l} 10,000 \text{ ppm} + = .01 \\ 1,000 \text{ ppm} + = .001 \end{array}$$

Calculation for the 500 ppm ROE: $\begin{array}{l} 100 \text{ ppm} + = .0001 \\ 10 \text{ ppm} + = .00001 \end{array}$

$$\text{ROE} = [(0.4546)(\text{H}_2\text{S concentration})(Q)]^{(.6258)}$$

EXAMPLE: If a well/facility has been determined to have 650 ppm H₂S in the gas mixture and the well/facility is producing at a gas rate of 200 MCFD then:

$$\begin{array}{ll} \text{ROE for 100 ppm} & \text{ROE} = [(1.589)(.00065)(200,000)]^{.6258} \\ & \text{ROE} = 28.1' \\ \text{ROE for 500 ppm} & \text{ROE} = [(0.4546)(.00065)(200,000)]^{.6258} \\ & \text{ROE} = 12.8' \end{array}$$

These calculations will be forwarded to the appropriate NMOC district office when applicable.

PUBLIC EVACUATION PLAN

When the supervisor has determined that the general public will be involved, the following plan will be implemented.

1. Notification of the emergency response agencies of the hazardous condition and implement evacuation procedures.
2. A trained person in H₂S safety shall monitor with detection equipment the H₂S concentration, wind and area of exposure. This person will determine the outer perimeter of the hazardous area. The extent of the evacuation area will be determined from the data being collected. Monitoring shall continue until the situation has been resolved. All monitoring equipment shall be UL approved for use in Class I Groups A, B, C & D, Division I hazardous locations. All monitors will have a minimum capability of measuring H₂S, oxygen, and flammable values.
3. Law enforcement shall be notified to set up necessary barriers and maintain such for the duration of the situation as well as aid in the evacuation procedure.
4. The company representative shall stay in communication with all agencies throughout the duration of the situation and inform such agencies when the situation has been contained and the affected area is safe to enter.

PROCEDURE FOR IGNITING AN UNCONTROLLABLE CONDITION

The decision to ignite a well should be a last resort with one, if not both, of the following conditions:

1. Human life and/or property are endangered.
2. There is no hope of bringing the situation under control with the prevailing conditions at the site.

Instructions for Igniting the Well:

1. Two people are required. They must be equipped with positive pressure, self-contained breathing apparatus and "D"-ring style, full body, OSHA approved safety harness. Non-flammable rope will be attached.
2. One of the people will be a qualified safety person who will test the atmosphere for H₂S, oxygen and LFL. The other person will be the designated company representative.
3. Ignite upwind from a distance no closer than necessary. Make sure that the ignition site has the maximum escape avenue available. A 25mm flare gun with a range of approximately +/- 500 feet shall be used to ignite the gas.
4. Before igniting, check for the presence of combustible gases.
5. After igniting, continue emergency actions and procedures as before.

REQUIRED EMERGENCY EQUIPMENT

1. Breathing Apparatus

- Rescue Packs (SCBA) – 1 unit shall be placed at each breathing area, 2 shall be stored in the safety trailer.
- Work / Escape Packs – 4 packs shall be stored on the rig floor with sufficient air hose not to restrict work activity.
- Emergency Escape Packs – 4 packs shall be stored in the doghouse for emergency evacuation.

2. Signage and Flagging

- One Color Code Condition Sign will be placed at the entrance to the site reflecting the possible conditions at the site.
- A Colored Condition flag will be on display reflecting the condition at the site at that time.

3. Briefing Area

- Two perpendicular areas will be designated by signs and readily accessible.

4. Windsocks

- Two windsocks will be placed in strategic locations, visible from all angles.

5. H2S Detectors and Alarms

- The stationary detector with three (3) sensors will be placed in the upper dog house if equipped, set to visually alarm @ 10 ppm and audible alarm @ 15 ppm. Calibrate a minimum of every 30 days or as needed. The three sensors will be placed in the following places: (Gas sample tubes will be stored in the safety trailer):
 - Rig Floor
 - Bell Nipple
 - End of flow line or where well bore fluid is being discharged

6. Auxiliary Rescue Equipment

- Stretcher
- Two OSHA full body harnesses
- 100' of 5/8" OSHA approved rope
- One 20 lb. Class ABC fire extinguisher
- Communication via cell phones on location and vehicles on location

USING SELF-CONTAINED BREATHING AIR EQUIPMENT (SCBA)

1. SCBA should be worn when any of the following are performed:
 - Working near the top or on top of a tank
 - Disconnecting any line where H₂S can reasonably be expected.
 - Sampling air in the area to determine if toxic concentrations of H₂S exist.
 - Working in areas where over 10 ppm of H₂S has been detected.
 - At any time there is a doubt of the level of H₂S in the area.
2. All personnel shall be trained in the use of SCBA prior to working in a potentially hazardous location.
3. Facial hair and standard eyeglasses are not allowed with SCBA.
4. Contact lenses are never allowed with SCBA.
5. When breaking out any line where H₂S can reasonably be expected.
6. After each use, the SCBA unit shall be cleaned, disinfected, serviced and inspected.
7. All SCBA shall be inspected monthly.

RESCUE & FIRST AID FOR VICTIMS OF H₂S POISONING

- Do not panic.
- Remain calm and think.
- Put on the breathing apparatus.
- Remove the victim to the safe breathing area as quickly as possible, upwind and uphill from source or crosswind to achieve upwind.
- Notify emergency response personnel.
- Provide artificial respiration and/or CPR as necessary.
- Remove all contaminated clothing to avoid further exposure.
- A minimum of two (2) personnel on location shall be trained in CPR and First Aid.

TOXIC EFFECTS OF H₂S POISONING

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity-1.192) and is colorless and transparent. Hydrogen Sulfide is almost as toxic as Hydrogen Cyanide and is 5-6 times more toxic than Carbon Monoxide. Occupational exposure limits for Hydrogen sulfide and other gasses are compared below in Table 1. Toxicity table for H₂S and physical effects are shown in Table II.

Table 1
Permissible Exposure Limits of Various Gasses

| Common Name | Symbol | Sp. Gravity | TLV | STEL | IDLH |
|------------------|------------------|-------------|----------|------------|---------|
| Hydrogen Cyanide | HCN | .94 | 4.7 ppm | C | |
| Hydrogen Sulfide | H ₂ S | 1.192 | 10 ppm | 15 ppm | 100 ppm |
| Sulfide Dioxide | SO ₂ | 2.21 | 2 ppm | 5 ppm | |
| Chlorine | CL | 2.45 | .5 ppm | 1 ppm | |
| Carbon Monoxide | CO | .97 | 25 ppm | 200 ppm | |
| Carbon Dioxide | CO ₂ | 1.52 | 5000 ppm | 30,000 ppm | |
| Methane | CH ₄ | .55 | 4.7% LEL | 14% UEL | |

Definitions

- A. TLV – Threshold Limit Value is the concentration employees may be exposed to based on a TWA (time weighted average) for eight (8) hours in one day for 40 hours in one (1) week. This is set by ACGIH (American Conference of Governmental Hygienists and regulated by OSHA.
- B. STEL – Short Term Exposure Limit is the 15 minute average concentration an employee may be exposed to providing that the highest exposure never exceeds the OEL (Occupational Exposure Limit). The OEL for H₂S is 19 PPM.
- C. IDLH – Immediately Dangerous to Life and Health is the concentration that has been determined by the ACGIH to cause serious health problems or death if exposed to this level. The IDLH for H₂S is 100 PPM.
- D. TWA – Time Weighted Average is the average concentration of any chemical or gas for an eight (8) hour period. This is the concentration that any employee may be exposed to based on an TWA.

TABLE II
Toxicity Table of H₂S

| Percent % | PPM | Physical Effects |
|-----------|------|---|
| .0001 | 1 | Can smell less than 1 ppm. |
| .001 | 10 | TLV for 8 hours of exposure |
| .0015 | 15 | STEL for 15 minutes of exposure |
| .01 | 100 | Immediately Dangerous to Life & Health. Kills sense of smell in 3 to 5 minutes. |
| .02 | 200 | Kills sense of smell quickly, may burn eyes and throat. |
| .05 | 500 | Dizziness, cessation of breathing begins in a few minutes. |
| .07 | 700 | Unconscious quickly, death will result if not rescued promptly. |
| .10 | 1000 | Death will result unless rescued promptly. Artificial resuscitation may be necessary. |

PHYSICAL PROPERTIES OF H₂S

The properties of all gases are usually described in the context of seven major categories:

COLOR
ODOR
VAPOR DENSITY
EXPLOSIVE LIMITS
FLAMMABILITY
SOLUBILITY (IN WATER)
BOILING POINT

Hydrogen Sulfide is no exception. Information from these categories should be considered in order to provide a fairly complete picture of the properties of the gas.

COLOR – TRANSPARENT

Hydrogen Sulfide is colorless so it is invisible. This fact simply means that you can't rely on your eyes to detect its presence, a fact that makes the gas extremely dangerous to be around.

ODOR – ROTTEN EGGS

Hydrogen Sulfide has a distinctive offensive smell, similar to "rotten eggs." For this reason it earned its common name "sour gas." However, H₂S, even in low concentrations, is so toxic that it attacks and quickly impairs a victim's sense of smell, so it could be fatal to rely on your nose as a detection device.

VAPOR DENSITY – SPECIFIC GRAVITY OF 1.192

Hydrogen Sulfide is heavier than air so it tends to settle in low-lying areas like pits, cellars or tanks. If you find yourself in a location where H₂S is known to exist, protect yourself. Whenever possible, work in an area upwind and keep to higher ground.

EXPLOSIVE LIMITS – 4.3% TO 46%

Mixed with the right proportion of air or oxygen, H₂S will ignite and burn or explode, producing another alarming element of danger besides poisoning.

FLAMMABILITY

Hydrogen Sulfide will burn readily with a distinctive clear blue flame, producing Sulfur Dioxide (SO₂), another hazardous gas that irritates the eyes and lungs.

SOLUBILITY – 4 TO 1 RATIO WITH WATER

Hydrogen Sulfide can be dissolved in liquids, which means that it can be present in any container or vessel used to carry or hold well fluids including oil, water, emulsion and sludge. The solubility of H₂S is dependent on temperature and pressure, but if conditions are right, simply agitating a fluid containing H₂S may release the gas into the air.

BOILING POINT – (-76 degrees Fahrenheit)

Liquefied Hydrogen Sulfide boils at a very low temperature, so it is usually found as a gas.

**SURFACE USE AND OPERATIONS PLAN FOR
DRILLING, COMPLETION, AND PRODUCING**

**Murchison Oil & Gas, Inc.
Carbon Valley 26 Fed Com #1-H
SL: 1980' FSL & 250' FEL, UNIT I
BHL: 1980' FSL & 330' FWL, UNIT L
Sec 26, T16S, R27E
Eddy County, New Mexico**

LOCATED

Approximately 11 miles NE of Artesia, New Mexico.

OIL & GAS LEASE

SHL: LS# NM NM 114347

BHL: LS# NM NM 120349

BOND COVERAGE

NM 2163

POOL

Dog Canyon; Wolfcamp

OIL & GAS RECORD LESSEE

Lessee: Murchison Oil & Gas, Inc., 1100 Mira Vista Blvd., Plano, TX 75093

Operating Rights: Murchison Oil & Gas, Inc., 1100 Mira Vista Blvd., Plano, TX 75093

SURFACE OWNER

Bureau of Land Management

MINERAL OWNER

Bureau of Land Management

GRAZING TENANT

Bogle Ltd Co. LLC, P.O. Box 460, Dexter, NM 88230 (575) 433-3500

EXHIBITS

- A. Well Location & Acreage Dedication Map
- B. Area Road Map
- C-1 & C-2 Vicinity Oil & Gas Map
- D. Topographic & Location Verification Map
- E-1---E-2 Proposed Lease Road and Pad Layout Map
- F. Drilling Rig Layout
- G. BOPE Schematic
- H. Choke Manifold Schematic

This well will be drilled to a BHL of approximately 6235' TVD, and approximately 10705' MD.

EXISTING ROADS

Exhibit A is a portion of a section map showing the location of the proposed well as staked.

Exhibit B is a map showing existing roads in the vicinity of the proposed well site.

Directions to well location: From the junction of Hwy. 82 and Southern Union (CR 202), go North on CR202 approx. 3.0 miles; veer Northeast and go approx. 1.2 miles; veer Northwest and go approx. 2.2 miles. Turn right and go Northeast approx. 800 feet. Turn North and go approx. 1900' feet. Location is approx. 200 feet West.

ACCESS ROADS

Length and Width

Proposed access road is approximately 14714.8' of existing road and 34' of new road (approx. 2.787 miles) long and 50' wide (Exhibit E-1 thru E-7). Murchison Oil & Gas, Inc. has agreements with the surface owners for right-of-way up to proposed lease road and for the additional lease road to proposed well.

Surface Material

Six inches of caliche and water, compacted and graded.

Maximum Grade

Less than three percent

Turnouts

None needed

Drainage Design

N/A

Culverts

None needed

Gates and Cattle Guards

None required

LOCATION OF EXISTING WELLS

The locations of existing wells in Section 26 are shown on Exhibit C-1 and C-2.

LOCATION OF EXISTING AND/OR PROPOSED FACILITIES

Necessary production facilities for this well will be located on the well pad.

LOCATION AND TYPE OF WATER SUPPLY

It is planned to drill the proposed well with a cut-brine water system or with produced water. The water will be obtained from either a private water well owner or a commercial source and will either be piped to location from a nearby water well or will be hauled to location by truck over existing and proposed lease roads as shown on Exhibit E.

SOURCE OF CONSTRUCTION MATERIALS

Caliche required for the construction of the location pad and access road will be obtained from caliche on the location or from the nearest BLM-approved pit.

METHODS OF HANDLING WASTE DISPOSAL

All drilling fluid will be circulated over shaker(s) with cuttings discharged into roll off container.

Fluid and fines below shaker(s) will be circulated with transfer pump through centrifuge(s) or solids separator with cuttings and fines discharged into roll off container.

Fluid will be continuously re-circulated through equipment with polymer added to aid separation of cutting fines.

Roll-off containers will be lined and de-watered with fluids re-circulated into system.

Additional tank will be used to capture unused drilling fluid or cement returns from casing jobs.

This equipment will be maintained by solids control personnel and/or rig crews on location.

Cuttings will be hauled to one of the following, depending on which rig is available to drill well:

CRI (permit number R9166)
or
GMI (permit number 711-019-001)

ANCILLARY FACILITIES

None required.

WELL SITE LAYOUT

Exhibit F shows the relative location and dimensions of the well pad, mud pits, cuttings containers and trash pit, and the location of major rig components. Operator requests V-door be positioned to the East, and the steel pits located to the North.

The ground surface at the drilling location is essentially flat.

A Closed-Loop System will be used.

The pad area has been staked and flagged.

PLANS FOR RESTORATION OF THE SURFACE

After finishing drilling and/or completion operations, all equipment and other material not needed for further operations will be removed. The location will be cleared of all trash and junk to leave the site in an as aesthetically pleasing condition as possible.

Any unguarded pits containing fluids will be fenced until they are filled.

If the proposed well is non productive, all rehabilitation and/or vegetation requirements of the Bureau of Land Management and the United States Geological Survey will be complied with and will be accomplished as expeditiously as possible.

OTHER INFORMATION

Topography

The land surface at the well site is small, rolling hills.

Soil

Loamy soil shallow to caliche and raw Gypsum.

Flora and Fauna

The vegetation consists of creosote, mesquite, yucca, prickly pear, Mormon tea, cane cholla, pencil cholla, horse creeper and various grasses. Faunal species include pronghorn antelope, mule deer, coyote, badger, rabbits, and various snakes, small mammals, birds and reptiles.

Ponds and Streams

There are no rivers, lakes, ponds, or streams in the area.

Residences and Other Structures

There are no residences within one mile of the proposed well site.

Archaeological, Historical, and Cultural sites

An Archaeological Survey has been sent to the BLM Office.

Land Use

Grazing

OPERATOR'S REPRESENTATIVES

Arnold Nall
1100 Mira Vista Blvd.
Plano, TX 75093-4698
Office Phone: (972) 931-0700
Cell Phone: (214) 415-3010

Randy Ford
415 W. Wall Street, Suite 1700
Midland, TX 79701
Office Phone: (432) 682-0440
Cell Phone: (432) 559-2222


Murchison Oil & Gas, Inc.
Carbon Valley 26 Fed Com #1-H
SL: 1980' FSL & 250' FEL, UNIT I
BHL: 1980' FSL & 330' FWL, UNIT L
Sec 26, T16S, R27E
Eddy County, New Mexico

CERTIFICATION

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which presently exist; that the statements made in this plan are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed by Murchison Oil & Gas, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved.

Date

1/22/10


Arnold Nall
VP, Operations
Murchison Oil & Gas, Inc.

NMCRIS INVESTIGATION ABSTRACT FORM (NIAF)

| | | | |
|---|---|---|-----------------------------------|
| 1. NMCRIS Activity No.: 116,176 | 2a. Lead (Sponsoring) Agency: BLM-CFO | 2b. Other Permitting Agency(ies): State of New Mexico | 3. Lead Agency Report No.: |
|---|---|---|-----------------------------------|

| | |
|--|--|
| 4. Title of Report: A Cultural Resource Survey for the Carbon Valley "26" Federal Com No. 1H Well Pad and Access Road Author(s) Justin Rein | 5. Type of Report <input checked="" type="checkbox"/> Negative <input type="checkbox"/> Positive |
|--|--|

| |
|---|
| 6. Investigation Type <input type="checkbox"/> Research Design <input checked="" type="checkbox"/> Survey/Inventory <input type="checkbox"/> Test Excavation <input type="checkbox"/> Excavation <input type="checkbox"/> Collections/Non-Field Study <input type="checkbox"/> Overview/Lit Review <input type="checkbox"/> Monitoring <input type="checkbox"/> Ethnographic study <input type="checkbox"/> Site specific visit <input type="checkbox"/> Other |
|---|

| | |
|---|---|
| 7. Description of Undertaking (what does the project entail?): The proposed undertaking involves a pedestrian cultural resource survey for the proposed Murchison Oil and Gas, Inc. Carbon Valley "26" Federal Com No. 1H well location and associated access road. The proposed well will impact an area no greater than 400 ft by 400 ft yet a 600 ft by 600 ft block of land was surveyed. Likewise, the proposed access road will impact a strip of land no greater than 50 ft wide, yet a 100 ft wide corridor was surveyed to ensure the protection of any cultural resources. | 8. Dates of Investigation: January 5, 2010 9. Report Date: January 8, 2010 |
|---|---|

| | |
|---|---|
| 10. Performing Agency/Consultant: Boone Archaeological Services, LLC 2030 North Canal Carlsbad, NM 88220 575-885-1352 Principal Investigator: Danny Boone Field Supervisor: Justin Rein Field Personnel Names: Justin Rein | 11. Performing Agency/Consultant Report No.: BAS-12-09-38 12. Applicable Cultural Resource Permit No(s): BLM Permit No.: 190-2920-08-K NM State Permit No.: NM-10-157-M |
|---|---|

| | |
|--|---|
| 13. Client/Customer (project proponent): Murchison Oil & Gas, Inc. Contact: Vicki Johnston Address: 1100 Mira Vista Blvd. Plano, Texas 75093-4698 Phone: (281) 468-2448 | 14. Client/Customer Project No.: N/A |
|--|---|

15. Land Ownership Status (Must be indicated on project map):

| Land Owner | Acres Surveyed | Acres in APE |
|---|----------------|--------------|
| Bureau of Land Management – Carlsbad Field Office (BLM-CFO) | 8.15 | 4.17 |
| State of New Mexico | 3.67 | 1.49 |
| | | |
| TOTALS | 11.82 | 5.66 |

16. Records Search(es):

| | | |
|---|---|-----------------------|
| Date(s) of ARMS File Review: January 4, 2009 | Name of Reviewer(s): Justin Rein | |
| Date(s) of NR/SR File Review: January 4, 2009 | Name of Reviewer(s): Justin Rein | |
| Date(s) of Other Agency File Review: January 5, 2009 | Name of Reviewer(s): Justin Rein | Agency BLM-CFO |

Three previously recorded sites (LA 142360, LA 142599, and LA 160055) were found within 0.25 miles of the project area. One of these sites, LA 142360, is within 500 ft. None of these sites will be affected by the current undertaking.

17. Survey Data:

- a. Source Graphics ☒ NAD 27 ☐ NAD 83
☒ USGS 7.5' (1:24,000) topo map ☐ Other topo map, Scale:
☒ GPS Unit Accuracy ☐ <1.0m ☒ 1-10m ☐ 10-100m ☐ >100m

b. USGS 7.5' Topographic Map Name USGS Quad Code

| | |
|--------------------------------|----------|
| Diamond Mound, New Mexico 1951 | 32104-H2 |
| | |

c. County(ies): Eddy County**17. Survey Data (continued):****d. Nearest City or Town:** Artesia, New Mexico**e. Legal Description:**

| Township (N/S) | Range (E/W) | Section | 1/4 | 1/4 | 1/4 |
|----------------|-------------|---------|------|-------|-------|
| 16 South | 27 East | 25 | E1/2 | NE1/4 | SE1/4 |
| | | 25 | E1/2 | SE1/4 | SW1/4 |
| 16 South | 27 East | 26 | W1/2 | NW1/4 | SW1/4 |
| | | | | | |

Projected legal description? Yes [], No [] Unplatted []

- f. Other Description (e.g. well pad footages, mile markers, plats, land grant name, etc.): The proposed Carbon Valley "26" Federal Com No. 1H well location is centered 1,980 feet from the south line and 250 feet from the east line of Section 26, Township 16 South, Range 27 East. The proposed access road begins at the northern margin of an existing caliche-capped lease road along the base of Dog Canyon Draw and travels approximately 1,700 ft north thence 35 ft west where it terminates at the southeastern margin of the proposed well location. Section 25 is an irregular section, the template was anchored in the northeast and northwest corners of the section for the above legal description.

18. Survey Field Methods:

Intensity: ☒ 100% coverage ☐ <100% coverage

Configuration: ☒ block survey units: 600 ft by 600 ft ☒ linear survey units (l x w): 1,550 ft long by 100 ft wide
☐ other survey units (specify):

Scope: ☒ non-selective (all sites recorded) ☐ selective/thematic (selected sites recorded)

Coverage Method: ☒ systematic pedestrian coverage ☐ other method (describe)

Survey Interval (m): 15m (50 ft) Crew Size: 1 Fieldwork Dates: January 5, 2010

Survey Person Hours: 4.0 Recording Person Hours: 0 Total Hours: 4.0

Additional Narrative: In order to protect any cultural resources, a 600 ft by 600 ft was surveyed around the staked well center utilizing linear transect intervals spaced no more than 15 m (50 ft) apart. Approximately 185 ft of the proposed access road lies within the block survey. A 100 ft wide corridor was surveyed along the remainder of the staked access road centerline utilizing the same 50 ft wide linear transect. The survey encompassed a total of 11.82 acres on both State of New Mexico property (3.67 acres) and Federal property (8.15 acres) with the BLM-CFO acting as lead agency.

19. Environmental Setting (NRCS soil designation; vegetative community; elevation; etc.): The project area is located along the northern flank of Dog Canyon Draw, roughly 10 miles east-northeast of Artesia, New Mexico. Elevation ranges from 3,430 ft to 3,490 above mean sea level. Overall, the terrain slopes gradually downhill to the south, towards Dog Canyon Draw, at a grade of roughly two percent. Local soils are of the Reeves-Gypsum land-Cottonwood association as defined by the Soil Conservation Service of the U.S. Department of Agriculture. Local vegetation is typical of Chihuahuan Desert scrub and includes various grasses, mesquite, acacia, creosote, prickly pear, horse creeper, and barrel cacti, yucca, Mormon tea, and various low forbs.

Meteorological data was obtained for the nearby City of Artesia, New Mexico from the Western Regional Climate Center (WRCC) online database. From 1914 to 2004, Artesia received an average annual precipitation of 11.87 inches. During the same time, Artesia had an average high temperature of 76.9 degrees Fahrenheit and an average low temperature of 43.8 degrees Fahrenheit. January was the coldest month averaging 56.8 degrees Fahrenheit, while July was the warmest on average at 94.8 degrees Fahrenheit.

20. a. Percent Ground Visibility: 80%

b. Condition of Survey Area (grazed, bladed, undisturbed, etc.): Due to the vegetative ground cover, surface visibility averaged 80 percent at the time of survey. The proposed well location is located west of two large north – south trending overhead transmission lines. Access will be afforded the well via a two-track road along the western of the two transmission lines which will necessitate upgrading. A caliche lease road is located at the southern terminus of the lease road upgrade, traveling from southwest to northeast along the base of Dog Canyon Draw. Additional oil and gas exploration is visible in the surrounding area while the remainder of the project area remains otherwise undeveloped and susceptible to natural aeolean and alluvial activities and openly grazing cattle.

21. CULTURAL RESOURCE FINDINGS ☐ Yes, See Page 3 ☒ No, Discuss Why: The project area is situated across a gradually sloping yet overall flat, exposed plain which may have been less desirable for long term occupation.

22. Required Attachments (check all appropriate boxes):

- ☒ USGS 7.5 Topographic Map with sites, isolates, and survey area clearly drawn
- ☒ Copy of NMCRIS Mapserver Map Check
- ☐ LA Site Forms - new sites (*with sketch map & topographic map*)
- ☐ LA Site Forms (update) - previously recorded & un-relocated sites (*first 2 pages minimum*)
- ☐ Historic Cultural Property Inventory Forms
- ☒ List and Description of isolates, if applicable
- ☐ List and Description of Collections, if applicable

23. Other Attachments:

- ☐ Photographs and Log
- ☒ Other Attachments

(Describe): Survey plats provided by Murchison Oil & Gas, Inc.

24. I certify the information provided above is correct and accurate and meets all applicable agency standards.

Principal Investigator/Responsible Archaeologist: Justin Rein

Signature



Date

1-8-10

Title (if not PI): Crew Chief

25. Reviewing Agency:
Reviewer's Name/Date

Accepted () Rejected ()

Tribal Consultation (if applicable): ☐ Yes ☐ No

26. SHPO

Reviewer's Name/Date:

HPD Log #:

SHPO File Location:

Date sent to ARMS:

CULTURAL RESOURCE FINDINGS

[fill in appropriate section(s)]

| | | |
|------------------------------------|---|----------------------------|
| 1. NMCRIS Activity No.: 116,176 | 2. Lead (Sponsoring) Agency: BLM - CFO | 3. Lead Agency Report No.: |
|------------------------------------|---|----------------------------|

SURVEY RESULTS:

Sites discovered and registered: 0

Sites discovered and NOT registered: 0

Previously recorded sites revisited *(site update form required)*: 0

Previously recorded sites not relocated *(site update form required)*: 0

TOTAL SITES VISITED: 0

Total isolates recorded: 3 Non-selective isolate recording? ☒

Total structures recorded *(new and previously recorded, including acequias)*: 0

MANAGEMENT SUMMARY: No significant cultural materials were encountered during the survey. As such, archaeological clearance is recommended for the proposed Carbon Valley "26" Federal Com No. 1H well location and associated access road. If any additional cultural materials are encountered during any phase of construction, work at that location should cease and archaeologists with the BLM-CFO should be notified immediately.

IF REPORT IS NEGATIVE YOU ARE DONE AT THIS POINT.

SURVEY LA NUMBER LOG

Sites Discovered:

| LA No. | Field/Agency No. | Eligible? (Y/N, applicable criteria) |
|--------|------------------|--------------------------------------|
| | | |
| | | |
| | | |

Previously recorded revisited sites:

| LA No. | Field/Agency No. | Eligible? (Y/N, applicable criteria) |
|--------|------------------|--------------------------------------|
| | | |
| | | |
| | | |

MONITORING LA NUMBER LOG *(site form required)*

Sites Discovered *(site form required)* :

Previously recorded sites *(Site update form required)*:

| LA No. | Field/Agency No. | LA No. | Field/Agency No. |
|--------|------------------|--------|------------------|
| | | | |
| | | | |


Areas outside known nearby site boundaries monitored? Yes ☐, No ☐ If no explain why:

TESTING & EXCAVATION LA NUMBER LOG *(site form required)*

Tested LA number(s) Excavated LA number(s)

| | |
|--|--|
| | |
| | |

SURVEY FOR THE CARBON VALLEY "26" FEDERAL COM No. 1H WELL PAD AND ACCESS ROAD



**BUREAU OF LAND MANAGEMENT
CASE RECORDATION
(LIVE) SERIAL REGISTER PAGE**

BHL

Run Date/Time: 02/02/10 07:12 AM

Page 1 of 1

01 12-22-1987;101STAT1330;30USC181 ET SEQ

Total Acres

Serial Number

Case Type 312021: O&G LSE COMP PD -1987

800.000

NMNM-- - 120349

Commodity 459: OIL & GAS L

Case Disposition: AUTHORIZED Case File Juris:

Serial Number: NMNM-- - 120349

| Name & Address | | | Int Rel | %Interest |
|----------------|-------------|------------------|---------|--------------|
| CHASE OIL CORP | PO BOX 1767 | ARTESIA NM 88211 | LESSEE | 100.00000000 |

Serial Number: NMNM-- - 120349

| Mer Twp Rng | Sec | SType | Nr Suff | Subdivision | District/Resource Area | County | Mgmt Agency |
|--------------------|-----|-------|---------|-------------|------------------------|--------|---------------------|
| 23 0160S 0270E 024 | | ALIQ | | N2,SW; | CARLSBAD FO | EDDY | BUREAU OF LAND MGMT |
| 23 0160S 0270E 026 | | ALIQ | | NE,SW; | CARLSBAD FO | EDDY | BUREAU OF LAND MGMT |

Serial Number: NMNM-- - 120349

| Act Date | Code | Action | Action Remarks | Pending Office |
|------------|------|------------------------|-----------------------|----------------|
| 02/28/2008 | 387 | CASE ESTABLISHED | 200804008; | |
| 04/01/2008 | 299 | PROTEST FILED | /1/W ENVR LAW CTR | |
| 04/01/2008 | 299 | PROTEST FILED | /2/WILDEARTH GUARDIAN | |
| 04/16/2008 | 143 | BONUS BID PAYMENT RECD | \$1600.00; | |
| 04/16/2008 | 191 | SALE HELD | | |
| 04/16/2008 | 267 | BID RECEIVED | \$1360000.00; | |
| 04/23/2008 | 143 | BONUS BID PAYMENT RECD | \$1358400.00; | |
| 07/11/2008 | 298 | PROTEST DISMISSED | /1/ | |
| 07/11/2008 | 298 | PROTEST DISMISSED | /2/ | |
| 07/18/2008 | 237 | LEASE ISSUED | | |
| 07/18/2008 | 974 | AUTOMATED RECORD VERIF | BCO | |
| 08/01/2008 | 496 | FUND CODE | 05;145003 | |
| 08/01/2008 | 530 | RLTY RATE - 12 1/2% | | |
| 08/01/2008 | 868 | EFFECTIVE DATE | | |
| 07/31/2018 | 763 | EXPIRES | | |

| Line Nr | Remarks | Serial Number: NMNM-- - 120349 |
|---------|--|--------------------------------|
| 0002 | STIPULATIONS ATTACHED TO LEASE: | |
| 0003 | NM-11-LN SPECIAL CULTURAL RESOURCE | |
| 0004 | SENM-LN-1 CAVE - KARST OCCURRENCE AREA | |
| 0005 | SENM-S-17 SLOPES OR FRAGILE SOILS | |
| 0006 | SENM-S-21 CAVES AND KARST | |

**BUREAU OF LAND MANAGEMENT
CASE RECORDATION
(LIVE) SERIAL REGISTER PAGE**

SHL

Run Date/Time: 02/02/10 07:04 AM

Page 1 of 1

01 12-22-1987;101STAT1330;30USC181 ET SEQ

**Total Acres
280.000**

**Serial Number
NMNM-- - 114347**

Case Type 312021: O&G LSE COMP PD -1987

Commodity 459: OIL & GAS L

Case Disposition: AUTHORIZED Case File Juris:

Serial Number: NMNM-- - 114347

| Name & Address | Int Rel | %Interest |
|---|---------|--------------|
| THE BLANCO CO PO BOX 25968 ALBUQUERQUE NM 87125 | LESSEE | 100.00000000 |

Serial Number: NMNM-- - 114347

| Mer Twp Rng | Sec | SType | Nr Suff | Subdivision | District/Resource Area | County | Mgmt Agency |
|--------------------|------|-------|---------|---------------|------------------------|--------|---------------------|
| 23 0160S 0270E 026 | ALIQ | | | NW,N2SE,SWSE; | CARLSBAD FO | EDDY | BUREAU OF LAND MGMT |

Serial Number: NMNM-- - 114347

| Act Date | Code | Action | Action Remarks | Pending Office |
|------------|------|------------------------|-----------------------|----------------|
| 07/19/2005 | 387 | CASE ESTABLISHED | 200507026; | |
| 07/20/2005 | 191 | SALE HELD | | |
| 07/20/2005 | 267 | BID RECEIVED | \$154000.00; | |
| 08/11/2005 | 237 | LEASE ISSUED | | |
| 08/11/2005 | 974 | AUTOMATED RECORD VERIF | LR | |
| 09/01/2005 | 496 | FUND CODE | 05;145003 | |
| 09/01/2005 | 530 | RLTY RATE - 12 1/2% | | |
| 09/01/2005 | 868 | EFFECTIVE DATE | | |
| 01/03/2006 | 963 | CASE MICROFILMED | | |
| 12/22/2009 | 140 | ASGN FILED | BLANCO/MURCHISON OI;1 | FLUIDS TEAM |
| 08/31/2015 | 763 | EXPIRES | | |

Serial Number: NMNM-- - 114347

| Line Nr | Remarks |
|---------|--|
| 02 | STIPULATIONS ATTACHED TO LEASE: |
| 03 | NM-11-LN SPECIAL CULTURAL RESOURCE LEASE |
| 04 | NOTICE |
| 05 | SENM-LN-1 CAVE - KARST OCCURRENCE AREA |
| 06 | SENM-S-17 SLOPES OR FRAGILE SOILS |
| 07 | GYPSUM SOILS |
| 08 | SENM-S-21 CAVES AND KARST |



FEDERAL EXPRESS

January 29, 2010

United States Department of the Interior
Bureau of Land Management
Carlsbad Field Office
620 E. Greene St.
Carlsbad, NM. 88220-6292

**RE: CARBON VALLEY 26 FED COM #1-H
SEC. 26, T16S, R27E
EDDY CO., NM.**

To Whom It May Concern:

Please find enclosed the following:

- 1) Form 3160-3 - Application for Permit to Drill, Form C-102, plus attachments – (6 sets = 1 original + 5 copies)
- 2) Check #0052753 - \$6,500.00 - APD processing fee
- 3) Archaeological Report (6 copies)
- 4) Form C-144 CLEZ (6 copies)

Very truly yours,

MURCHISON OIL & GAS, INC.


Carla Tracy
Regulatory Coordinator

C:\CarbonValley26FedCom#1-H-BLMLtr-Fm3160-3-APD

Encl.

RECEIVED
BUREAU OF LAND MGMT
OFFICE
JAN 29 PM 12:29
BH

| BUREAU OF LAND MANAGEMENT | | VENDOR | CHECK DATE | | |
|---------------------------|-----------------|--|------------|-------------------|--------------------------|
| | | 2048 | 01/29/10 | | |
| INVOICE NUMBER | INVOICE DATE | | | DISCOUNT TAKEN | AMOUNT PAID |
| 12910CV261-H | 01/29/10 | 1532010 APD FEE-CARBON VLY 26 FED #1H Total: | | 0.00 0.00 | 6,500.00 6,500.00 |

BUREAU OF LAND MGMT
CARLSBAD FIELD OFFICE
777 EFD - X
BH
PM 12:29

Posted
2-1-10
CC
A. Amac

Murchison Oil & Gas, Inc.

1100 Mira Vista Blvd.
Plano, Texas 75093-4698
972-931-0700

Bank of America
Dallas Texas

CHECK NO.
0052753

DATE
01/29/10

AMOUNT
*****6,500.00

*****6,500 Dollars and 00 Cents

COPY

PAY
TO THE
ORDER
OF

BUREAU OF LAND MANAGEMENT
CARLSBAD FIELD OFFICE
620 E. GREENE ST
CARLSBAD NM 88220

Sandra J. Dwyer

THE BACK OF THIS DOCUMENT CONTAINS AN ARTIFICIAL WATERMARK—HOLD AT AN ANGLE TO VIEW

BUREAU OF LAND MANAGEMENT

BOND ABSTRACT

BLM BOND NO: NM2163
 DOCUMENT ID: US TREASURY NOTE
 CASE TYPE: 310434 O&G BOND ALL LANDS

DISPOSITION: ACCEPTED

NAME AND ADDRESS OF BOND PARTIES

B89000284 BONDED PRINCIPAL
 MURCHISON OIL & GAS INC
 1445 ROSS AVE NO 5300
 DALLAS TX 752022733

NAME AND ADDRESS OF SURETY PARTIES

SERIAL NUMBER(s):

BOND AREA: STATEWIDE
 TYPE OF LAND: FEDERAL-ALL RIGHTS
 BOND TYPE: TREASURY SECURITY

STATES COVERED: NM
 BOND AMOUNT:\$25,000

BONDED ACTIVITY/PURPOSE

COMMODITY(IES)

GENERAL LSE/DRILLING

OIL & GAS L

| ACTION CODE | ACTION DATE | ACTION TAKEN | ACTION REMARKS | PENDING |
|-------------|-------------|------------------------|--------------------|---------|
| 468 | 03/22/1993 | BOND FILED | | NM94364 |
| 469 | 04/29/1993 | BOND ACCEPTED | EFF 03/22/1993 | |
| 974 | 04/29/1993 | AUTOMATED RECORD VERIF | ST/JLV | |
| 478 | 04/20/1998 | RIDER FILED | | NM92100 |
| 247 | 05/01/1998 | FUTURE ACTION SUSPENSE | NOTE DUE 01/31/03; | |
| 479 | 05/01/1998 | RIDER ACCEPTED | EFF 04/20/98; | |
| 113 | 01/01/2003 | ADDTL INFO RECD | REPLACEMENT T-NOTE | |
| 247 | 01/01/2003 | FUTURE ACTION SUSPENSE | MATURES 11/15/07 | |
| 974 | 01/01/2003 | AUTOMATED RECORD VERIF | TF/TF | |

GENERAL REMARKS

LINE # REMARK

000 04/29/1993 REPLACEMENT BOND FOR BLM BOND NO. NM1732
 001 05/01/1998 - Rider changes US Treasury note security
 002 01/01/2003 - T-NOTE MATURES 11/15/07 - SECURITY CONTINUES AFTER MATURITY
 003 DATE BUT INTEREST TO MURCHISON STOPS UNLESS COMPANY REPLACES
 004 WITH NEW T-NOTE